PECTEC

PEC Technology (Thailand) Co.,Ltd

181, 183 Sukontasawat Rd., Ladphrao District Bangkok 10230

Tel: +66 2907 8521-4 , Fax: +66 2907 8525

Monday-Friday 08:00-17:00, Sat 8:00-12:00 GMT+7

Content

- Introduction
- Technical Specification
- System Test (Integration Test)
- Tender
 - Project Evaluation (Price Performance)
 - Required Documents

Introduction

1.2 MWh/2 MW BESS for substation

MEA's Pathum Wan Project

Install Energy Storage System Pilot Project at Pathum Wan substation

For support load without outage

BESS(1.2 MWh/2 MW) with the following Applications


- Load Leveling
- Power Backup
- Resynchronize


Load Leveling


ESS – On Grid mode ESS – On G
Charge Battery Disch

ESS – On Grid mode


Discharge Battery








Power Backup Case 3



Fault occurs in Microgrid Bus


Power Backup Case 4



Fault occurs in load bus

Resynchronize

ESS – On Grid mode Discharge Battery Relay send command to PCS to synchronous ESS to PM then disconnect SAM



PECTEC

Open

Close


Resynchronize

PM Feeder

ESS – On Grid mode Discharge Battery Relay send command to PCS to synchronous ESS to PM then disconnect SAM

Open

Close



PECTEC

Gas isolated switchgear (GIS)

- GIS model is from Siemens.
- GIS will be supplied by our partner.

MGC shall be able to perfectly coordinate with GIS.


Conceptual Design

Considering battery capacity @ 80% DOD

- Load Leveling (55 % of battery capacity)
 charges during low demand
 discharges during high demand
- 2. Power Backup (25 % of battery capacity) when the grid fails, the load disconnect from the grid BESS then supplies load (@ 2 MW for at least 10 min)
- 3. Resynchronize once the grid come back, safely reconnect to the grid



PLAN PROCESS (Tentative)



Technical Specification

Requirements for each main equipment

MEA's Pathum Wan Project

Main Equipment

Lithium Ion Battery

1.2MWh

Power Conversion System

2MW

Microgrid Controller

Gas Insulated Switchgear

Lithium Ion Battery

Type Test

IEC 62619 (Altitude simulation, Thermal cycling, Vibration, Shock Test, Short circuit,

Crush/Impact Test, Forced Discharge, Overcharge)

IEC 62620 (Discharge performance at 25°C, Discharge performance at low temperature, High

rate permissible current, Charge (capacity) retention and recovery, Internal a.c.

resistance, Internal d.c. resistance, Endurance in cycle, Endurance in storage at

constant voltage (permanent charge life) which conducted in company's lab)

UN/DOT 38.3 6th Editions or IEC 62281

(Altitude, Thermal cycling, Vibration, Shock, External Short Circuit, Impact or crush Which test conducted in an institute with ISO/IEC 17025)

PECTEC

Power Conversion System

Type Test

IEC 62109 (Which test conducted in an institute with ISO/IEC 17025)

Routine Test

- 1. A report presenting that the PCS comply with the *project requirements* (the issuer shall certified by ISO/IEC 17025 or recognized by MEA)
- 2. A report presenting that the PCS comply with MEA interconnection code

PCS Requirements

AC ratings

- .. Rate output power 2 MW
- 2. VAR Production 2 MVAR
- 3. AC three phase system

Function/Features

- 1. Power flow Operation : Four-Quadrant
- Positive and Negative Real Power Control
- 3. Capacitive and Inductive Reactive Power Control
- Combination of Real and Reactive Power Control
- 5. Low-Voltage Ride Through
- 6. Synchro-check
- 7. Withstanding fault current 25 kA for 3 sec without disconnection

Operation modes

- Remote control to start/stop and command Real and Reactive power
- . Automatic Load Leveling
- 3. Automatic Power Backup
- 4. Scheduled Power
 - Automatic Black Start

Communication with

MEA

- DNP3.0/IEC61850
- 2. TCP/IP

Efficiency

1. Efficiency of Power conversion >= 95%



MEA Interconnection Code (for PCS Test)

Testing Institute

Inverters must be tested by a testing agency or institute with ISO / IEC 17025 test laboratory standards for inverters. Or must been verified by the Metropolitan Electricity Authority

Type of Testing

Design Test (Test 1 unit per model)

Harmonic, Voltage Fluctuation or Flicker, DC power supply, Voltage range, Frequency range, Protection of the occurrence of island landings and Resynchronization after power is restored.

Routine Test (Test all units)

Voltage range, Frequency range, Protection of the occurrence of island landings and Resynchronization after power is restored.

MEA Interconnection Code

Testing methods

Harmonic Test

following IEEE 1547.1-2005 item 5.11.1

(measuring harmonic current when the inverter is operating at 33%, 66% and 100% of the rated current)

voltage fluctuations

following IEC 61000-3-5 for inverter with rating current greater than 75 A

• DC power supply test

following IEEE 1547.1-2005 item 5.6

(measuring direct current when the inverter is operating at 33%, 66% and 100% of the rated current)

MEA Interconnection Code

- Testing methods
 - Voltage range test

Overvoltage and Undervoltage

Frequency range test

Overfrequency and Underfrequency

Anti-Islanding measures

following IEC 62116

Resynchronize


following IEEE 1547.1 item 5.10

Power Conversion System

<u>Additional Test Report</u>

A test results (in graph or appropriate figure) presenting response time of switching operation.

Example



Change of the set point (0 kW to 500kW)



System Test

System integration test before and after system delivery, FAT and SAT

test list	FAT	SAT	notes
Applications	\checkmark	\checkmark	
Transition time	\checkmark	✓	
Short circuit withstanding	\checkmark		
Actual energy capacity		\checkmark	
Input/output power rating	\checkmark	\checkmark	
Roundtrip efficiency		\checkmark	
Expected service life test		\checkmark	
System response	\checkmark	✓	
Auxiliary power consumption		\checkmark	
Self-discharge of EES		\checkmark	
Voltage & frequency ranges	\checkmark		using grid simulator
Duty cycle round trip efficiency		\checkmark	
Black start output voltage	\checkmark		

PECTEC

Factory Acceptance Test (Integration Test)

To test the integrated system for following functions (4 MEA staffs will participate in the test)

- Application Test
 - Load Leveling
 - Power Backup
 - Resynchronization
- Transfer time between on-grid and off-grid mode
- Short Circuit Withstanding (25kA for 3s)
- Parameter & Performance Test (IEC 62933-2-1 items 6.2 and 6.3)
 - A small module or simulation can be used

PECTEC

IEC 62933-2-1: Parameter Test (item 6.2)

- Actual energy capacity test
- Input and output power rating test
- Roundtrip efficiency test
- Expected service life test (simulation is acceptable)
- System response test, step response time and ramp rate
- Auxiliary power consumption test
- Self-discharge of EES test
- Voltage range and frequency range test

Voltage range and frequency range test


- A tolerance on all the measurements of input power shall be within ±2%
- Test case 1: $U = U_{min}$ and $f = f_{min}$ with constant rated active power output
- Test case 2: $U = U_{max}$ and $f = f_{max}$ with constant rated active power output
- Test case 3: $U = U_{min}$ and $f = f_{min}$ with constant rated active power input
- Test case 4: $U = U_{max}$ and $f = f_{max}$ with constant rated active power input
- 1. The EES system shall be charged or discharged to 50% of full available energy level or specified energy capacity value agreed between system supplier and user.
- 2. Voltage at the POC shall be set to test case and frequency at the POC shall be set to test case
- 3. It shall be confirmed that the EES system can output rated active power for 5 min or a specified duration agreed between system supplier and user at the POC.

PECTEC

IEC 62933-2-1: Performance Test (item 6.3)

Duty cycle round trip efficiency test (item 6.3.3)

- a) The ESS shall be set to the initial desired available energy
- b) The ESS shall be subjected to the applicable duty cycle
- c) At the end of cycle, the ESS shall be returned to the initial available energy





IEC 62933-2-1: Performance Test (item 6.3)

Black start output voltage test (item 6.3.4)

- a) The power conversion subsystem shall be connected electrically to the POC, externally connected to the specified test load. The POC shall not be energized by any other power supply. No external auxiliary power source is allowed to feed the system in this test.
- b) The signal, which indicates the start of the black start, shall be input to the EES system.
- c) The entire voltage envelope of the POC during transition to the steady state shall be recorded to determine the tolerance band of the steady state voltage. The system provider and user should specify the recording interval.

PECTEC

FAT Location (Tentative)

The test will be held at Asefa's factory (Bangkok, Thailand)

Map: https://g.page/asefa?share







Site Acceptance Test

- Parameter & Performance Test (IEC 62933-2-1 items 6.2 and 6.3)
 - in case of some test topic can not test at SAT, contractor must test at FAT
 - the parameters, system response, step response time, and ramp rate, must be tested at both SAT and FAT

Final Acceptance Certificates

- After finished SAT, had to report the test and delivery plan, known as "Commissioning test", to the Metropolitan Electricity Authority for consideration.
- Commissioning test refer to standard IEC 62933-2-1 section 6.4 or equivalent.
- The contractor must submit an officer in charge of each device. To participate in the first power supply operation by coordinating with other parties to be completed before conducting the commissioning test and power distribution.
- The winner of the electronic tender will be responsible for all risks, expenses, working hours and related work until the Metropolitan Electricity Authority issues a Final Acceptance Certificates (FAC) letter.

Supervisor Requirements

- Must have at least 2 years of experience in installing and testing energy storage systems.
- Must have at least 3 years experience in installation and test work related to substation.

Tender

Project evaluation and required documents

Price Performance (Tentative)

Index	weight
Price	60%
Performance	40%

Required Documents

Battery

Type Test

- Document shows
 - IEC 62619
 - IEC 62620
 - UN/DOT 38.3 6th Editions or IEC 62281

Sale History

 The battery's proposed model must be produced from a manufacturer with a sales history of at least 2 countries and at least 2 years.

Required Documents

PCS

Type Test

Document shows IEC 62109

Routine Test

- Test report showing that PCS meets the requirements.
- Test report showing that PCS meets the MEA Interconnection Code

Sale History

 The PCS's proposed model must be produced from a manufacturer with a sales history of at least 2 countries and at least 2 years.

Test Report

Test results (in graph or appropriate figure)
 presenting response time of switching operation.



Required Documents

Microgrid Controller

Sale History

 The Microgrid's proposed model must be produced from a manufacturer with a sales history of at least 2 countries and at least 2 years.